ITEM: 6.12

# COMMITTEE OF ADJUSTMENT REPORT SUMMARY MINOR VARIANCE APPLICATION FILE NUMBER A081/23 148 VIA TEODORO, WOODBRIDGE

# THIS REPORT CONTAINS COMMENTS FROM THE FOLLOWING DEPARTMENTS & AGENCIES:

\*Please see **Schedule B** of this report for a copy of Development Planning and Agency correspondence.

Additional comments from departments and agencies may be received after the publication of the Staff Report. These comments will be processed as an addendum and posted on the City's Website.

DEPARTMENTS	Circulated	Comments Received	Conditions	Nature of Comments
Committee of Adjustment	$\boxtimes$	$\boxtimes$		Recommend Adjournment
Building Standards (Zoning Review)	$\boxtimes$	$\boxtimes$		General Comments
Building Inspection (Septic)	$\boxtimes$			No Comments Received to Date
Development Planning	$\boxtimes$			Application Under Review
Development Engineering				Recommend Approval/No Conditions
Parks, Forestry and Horticulture Operations				General Comments
By-law & Compliance, Licensing & Permits				General Comments
Development Finance	$\boxtimes$	$\boxtimes$		General Comments
Real Estate				
Fire Department	$\boxtimes$			No Comments Received to Date
AGENCIES	Circulated	Comments Received	Conditions	Nature of Comments
TRCA	$\boxtimes$	$\boxtimes$		General Comments
Ministry of Transportation (MTO)				
Region of York	$\boxtimes$	$\boxtimes$		General Comments
Alectra	$\boxtimes$	$\boxtimes$		General Comments
Bell Canada	$\boxtimes$			No Comments Received to Date
YRDSB				
YCDSB				
CN Rail				
CP Rail				
TransCanada Pipeline	$\boxtimes$			No Comments Received to Date
Metrolinx				
Propane Operator				

# **PUBLIC & APPLICANT CORRESPONDENCE**

\*Please see **Schedule C** of this report for a copy of the public & applicant correspondence listed below.

The deadline to submit public comments is noon on the last business day prior to the scheduled hearing date.

Comments and written public submissions received after the publication of this Staff Report will be processed as an addendum and posted on the City's Website.

All personal information collected because of this public meeting (including both written and oral submissions) is collected under the authority of the Municipal Act, the Municipal Freedom of Information and Protection of Privacy Act (MFIPPA), the Planning Act and all other relevant legislation, and will be used to assist in deciding on this matter. All personal information (as defined by MFIPPA), including (but not limited to) names, addresses, opinions and comments collected will become property of the City of Vaughan, will be made available for public disclosure (including being posted on the internet) and will be used to assist the Committee of Adjustment and staff to process this application.

Correspondence Type	Name	Address	Date Received (mm/dd/yyyy)	Summary
None				

PREVIOUS COA DECISIONS ON THE SUBJECT LAND		
*Please see <b>Schedule D</b> for a copy of the Decisions listed below		
File Number Date of Decision Decision Outcome		
MM/DD/YYYY		

PREVIOUS COA DECISIONS ON THE SUBJECT LAND  *Please see Schedule D for a copy of the Decisions listed below		
None	r lease see <b>Schedule B</b> lor	a copy of the Bedisions hated below

ADJOURN	NMENT HISTORY
* Previous hearing dates where this application	was adjourned by the Committee and public notice issued.
None	



# COMMITTEE OF ADJUSTMENT REPORT MINOR VARIANCE APPLICATION A081/23

148 VIA TEODORO, WOODBRIDGE

ITEM NUMBER: 6.12	CITY WARD #: 3
TILWINGWIBER. 0.12	OIT WARD #. 0
APPLICANT:	Anna-Marie Colosimo & Nicholas Carchidi
AGENT:	Array International Architects Inc.
PROPERTY:	148 Via Teodoro, Woodbridge
ZONING DESIGNATION:	See Below
VAUGHAN OFFICIAL PLAN (2010) DESIGNATION:	Vaughan Official Plan 2010 ('VOP 2010'): "Low-Rise Residential"
RELATED DEVELOPMENT APPLICATIONS:	None
PURPOSE OF APPLICATION:	Relief from the Zoning By-law is being requested to permit a proposed cabana and pool.

The following variances have been requested from the City's Zoning By-law:

The subject lands are zoned R3(EN) and subject to the provisions of exception 14.919 under Zoning By-law 001-2021, as amended.

#	Zoning By-law 001-2021	Variance requested
1	A minimum rear yard setback of 2.4 metres to the	To permit a minimum rear yard setback of
	proposed Residential Accessory Structure	0.5 metres to the prosed Residential
	(Cabana) is required.	Accessory Structure (Cabana).
2	A minimum interior side yard setback of 2.4 metres	To permit a minimum interior side yard
	to the proposed Residential Accessory Structure	setback of 0.5 metres to the proposed
	(Cabana) is required.	Residential Accessory Structure (Cabana).
3	A minimum distance of 0.6 metres shall be	To permit a minimum distance of 0.1 0.26
	required from any permitted encroachment to the	metres from the residential accessory
	nearest lot line [Section 4.13]	structure eaves to the interior side lot line.
		*Revised using Zoning Review Waiver
4	A minimum distance of 0.6 metres shall be	To permit a minimum distance of 0.1 0.25
	required from any permitted encroachment to the	metres from the residential accessory
	nearest lot line [Section 4.13]	structure eaves to the rear lot line.
		*Revised using Zoning Review Waiver
5	A minimum rear yard setback of 1.5 metres to the	To permit a minimum rear yard setback of
	proposed pool is required [Section 4.21].	0.9 metres to the proposed pool.
6	A minimum interior side yard setback of 1.5 metres	To permit a minimum interior side yard
	to the proposed pool is required [Section 4.21].	setback of 1.0 metres to the proposed pool.
7	The maximum height of a residential accessory	To permit the maximum height of 3.68 3.17
	structure (Cabana) shall be 3.0 metres [Section	metres for a residential accessory structure
	4.1.5].	(Cabana).
		*Revised using Zoning Review Waiver

# **HEARING INFORMATION**

**DATE OF MEETING:** Thursday, July 13, 2023

**TIME:** 6:00 p.m.

**MEETING LOCATION:** Vaughan City Hall, Woodbridge Room (2<sup>nd</sup> Floor), 2141 Major Mackenzie Drive

LIVE STREAM LINK: Vaughan.ca/LiveCouncil

# PUBLIC PARTICIPATION

If you would like to speak to the Committee of Adjustment at the meeting, either remotely or in person, please complete the Request to Speak Form and submit to cofa@vaughan.ca

If you would like to submit written comments, please quote file number above and submit by mail or email

Email: cofa@vaughan.ca

# **HEARING INFORMATION**

**Mail:** City of Vaughan, Office of the City Clerk, Committee of Adjustment, 2141 Major Mackenzie Drive, Vaughan, ON, L6A 1T1

To speak electronically, pre-registration is required by completing the Request to Speak Form on-line and submitting it to cofa@vaughan.ca no later than NOON on the last business day before the meeting.

THE DEADLINE TO REGISTER TO SPEAK ELECTRONICALLY OR SUBMIT WRITTEN COMMENTS ON THE ABOVE NOTED FILE(S) IS <u>NOON</u> ON THE LAST BUSINESS DAY BEFORE THE MEETING.

# **INTRODUCTION**

Staff and Agencies act as advisory bodies to the Committee of Adjustment. The comments contained in this report are presented as recommendations to the Committee.

Section 45(1) of the Planning Act sets the criteria for authorizing minor variances to the City of Vaughan's Zoning By-law. Accordingly, review of the application may consider the following:

That the general intent and purpose of the by-law will be maintained.

That the general intent and purpose of the official plan will be maintained.

That the requested variance(s) is/are acceptable for the appropriate development of the subject lands. That the requested variance(s) is/are minor in nature.

Public written and oral submissions relating to this application are taken into consideration by the Committee of Adjustment as part of its deliberations and final decision on this matter.

COMMITTEE OF ADJUSTMENT COMMENTS		
Date Public Notice Mailed:	June 30, 2023	
Date Applicant Confirmed Posting of Sign:	June 26, 2023	
Applicant Justification for Variances: *As provided by Applicant in Application Form	Site is small and construction was already completed by owner according to best site configuration.	
	• • • • • • • • • • • • • • • • • • • •	
	appear to be present. Please provide a revised site plan that accurately shows the layout of the rear yard.  Given the above comments, we are requesting an adjournment to provide additional time to work on the Application. If you wish to proceed with the Application as shown, Development Planning will not be in a position to provide a recommendation of support. The updated Site	
	Plan is required regardless on if changes are made to the cabana or not, as a plan that accurately shows the site will be needed for the Committee to review.	

# **COMMITTEE OF ADJUSTMENT COMMENTS** Applicant provided Zoning Review Waiver on June 30, 2023 to continue with a revised submission. On June 30, 2023, Zoning confirmed required variances, indicating that the height of the cabana was 3.42 metres (not 3.17 metres as provided in the Zoning Review Waiver). On June 30, 2023, the applicant was advised that the variance for height could not be increased to 3.42 metres and that adjournment of the application was required to accommodate statutory public notice. Was a Zoning Review Waiver (ZRW) Form submitted by Applicant: Yes \*ZRW Form may be used by applicant in instances where a revised submission is made, and zoning staff do not have an opportunity to review and confirm variances prior to the issuance of public notice. \*A revised submission may be required to address staff / agency comments received as part of the application review process. \*Where a zoning review has not been completed on a revised submission, an opportunity is provided to the applicant to adjourn the proposal prior to the issuance of public notice. **Adjournment Fees:** In accordance with Procedural By-law 069-2019, an Adjournment Fee is applicable to reschedule an application after the issuance of public notice where a request for adjournment has been provided to the applicant prior to the issuance of public notice. An Adjournment Fee can only be waived in instances where adjournment of an application is requested by the Committee or staff after the issuance of public notice **Committee of Adjustment Comments:** Staff are recommending adjournment of the application to accommodate statutory public notice (height variance increased based on zoning comments after the issuance of public notice). Committee of Adjustment Recommended An Adjournment Fee (\$591.00) is required to reschedule **Conditions of Approval:** the application.

BUILDING STANDARDS (ZONING) COMMENTS	
**See Schedule B for Building Standards (Zoning) Comments	
Building Standards Recommended Conditions of Approval:  None	

DEVELOPMENT PLANNING COMMENTS	
**See Schedule B for Development Planning Comments.	
Development Planning Recommended Conditions of Approval:  None	

# **DEVELOPMENT ENGINEERING COMMENTS**

Link to Grading Permit Link to Pool Permit Link to Curb Curt Permit Link Culvert Installation

The Owner/Applicant shall apply for a 'Pool Grading Permit' with the Development Engineering (DE) Department. Please visit the grading permits page at City of Vaughan website to learn how to apply for the Pool Permit. If you have any question about Pool Grading Permit, please contact the Development Engineering Department through email at DEPermits@vaughan.ca.

The proposed work by the Owner / Applicant is increasing the lot coverage on the subject property. The added hardscape may have impacts on the City's Storm Water management system. Development Engineering strongly encourages the Owner / Applicant introduce Low-Impact Development (LID) measures (e.g., bioswales, permeable pavers, rain gardens, rain barrels etc.) to reduce the impacts to the stormwater system. Should further information be required, please contact the Development Engineering COA reviewer.

The Development Engineering Department does not object to the Minor Variance application A081/23, subject to the following condition(s):

Development Engineering	None
Recommended Conditions of	
Approval:	

PARKS, FORESTRY &	HORTICULTURE (PFH) COMMENTS
Forestry has no comment at this time.	
PFH Recommended Conditions of Approval:	None

DEVELOPMENT FINANCE COMMENTS		
No comment no concerns		
Development Finance Recommended Conditions of Approval:	None	

BY-LAW AND COMPLIANCE, LICENSING AND PERMIT SERVICES COMMENTS			
No objections or comments			
BCLPS Recommended Conditions of Approval:  None			

BUILDING INSPECTION (SEPTIC) COMMENTS			
No comments received to date.			
Building Inspection Recommended Conditions of Approval:  None			

FIRE DEPARTMENT COMMENTS			
No comments received to date.			
Fire Department Recommended Conditions of Approval:  None			

SCHEDULES TO STAFF REPORT  *See Schedule for list of correspondence			
Schedule A	Schedule A Drawings & Plans Submitted with the Application		
Schedule B	Staff & Agency Comments		
Schedule C (if required) Correspondence (Received from Public & Applicant)			
Schedule D (if required)	Previous COA Decisions on the Subject Land		

Should the Committee find it appropriate to approve this application in accordance with request and the sketch submitted with the application, as required by Ontario Regulation 200/96, the following conditions have been recommended:

# SUMMARY OF RECOMMENDED CONDITIONS OF APPROVAL All conditions of approval, unless otherwise stated, are considered to be incorporated into the approval "if required". If a condition is no longer required after an approval is final and binding, the condition may be waived by the respective department or agency requesting conditional approval. A condition cannot be waived without written consent from the respective department or agency.

# DEPARTMENT / AGENCY CONDITION(S) DESCRIPTION

1 Committee of Adjustment An Adjournment Fee (\$591.00) is required to reschedule the application (from July 13, 2023 hearing).

2 Development Planning Joshua.cipolletta@yaughan.ca

# **IMPORTANT INFORMATION - PLEASE READ**

**CONDITIONS:** It is the responsibility of the owner/applicant and/or authorized agent to obtain and provide a clearance letter from respective department and/or agency (see condition chart above for contact). This letter must be provided to the Secretary-Treasurer to be finalized. All conditions must be cleared prior to the issuance of a Building Permit.

# **IMPORTANT INFORMATION - PLEASE READ**

**APPROVALS:** Making any changes to your proposal after a decision has been made may impact the validity of the Committee's decision.

An approval obtained from the Committee of Adjustment, where applicable, is tied to the building envelope shown on the plans and drawings submitted with the application and subject to the variance approval.

A building envelope is defined by the setbacks of the buildings and/or structures shown on the plans and drawings submitted with the application, as required by Ontario Regulation 200/96. Future development outside of an approved building envelope, where a minor variance was obtained, must comply with the provisions of the City's Zoning By-law.

Elevation drawings are provided to reflect the style of roof (i.e. flat, mansard, gable etc.) to which a building height variance has been applied. Where a height variance is approved, building height is applied to the style of roof (as defined in the City's Zoning By-law) shown on the elevation plans submitted with the application.

Architectural design features that are not regulated by the City's Zoning By-law are not to be considered part of an approval unless specified in the Committee's decision.

**DEVELOPMENT CHARGES:** That the payment of the Regional Development Charge, if required, is payable to the City of Vaughan before issuance of a building permit in accordance with the Development Charges Act and the Regional Development Charges By-law in effect at the time of payment.

That the payment of the City Development Charge, if required, is payable to the City of Vaughan before issuance of a building permit in accordance with the Development Charges Act and the City's Development Charges By-law in effect at the time of payment.

That the payment of the Education Development Charge if required, is payable to the City of Vaughan before issuance of a building permit in accordance with the Development Charges Act and the Boards of Education By-laws in effect at the time of payment


That the payment of Special Area Development charge, if required, is payable to the City of Vaughan before issuance of a building permit in accordance with the Development Charges Act and The City's Development Charge By-law in effect at the time of Building permit issuance to the satisfaction of the Reserves/Capital Department.


**NOTICE OF DECISION:** If you wish to be notified of the decision in respect to this application or a related Ontario Land Tribunal (OLT) hearing you must complete a Request for Decision form and submit to the Secretary Treasurer (ask staff for details). In the absence of a written request to be notified of the Committee's decision you will **not** receive notice.

# **SCHEDULE A: DRAWINGS & PLANS**



# VAUGHAN A081/23 - 148 Via Teodoro





#### NOTE:

The Contractor shall check all dimensions of the work and shall report discrepancies to the Architect before proceeding.

All drawings and specifications are the property of ARRAY INTERNATIONAL ARCHITECTS INC., which reserves its copyright with respect to this document. It shall not be duplicated, used or circulated for any other purpose than that for which it was Issued.

Written dimensions shall govern where they differ from scaled measurements. The Architect accepts no responsbillty for measurements scaled from the drawlngs.

The Architect is not responsible for the accuracy of survey, structural, mechanical, electrical, etc., information shown on this frawing, Refer to the appropriate consultant's drawings before proceeding with the work. Construction must conform to all applicable codes and requirements of authorities having jurisdiction. The contractor working from drawings not specifically marked fron construction must assume full responsibility and bear costs for any corrections or damages resulting of sald work.

04	Issued for M.V App. Site plan Updated (Rev-4)	29/6/23	
03	Issued for M.V App. Site plan Updated (Rev-1)	27/6/23	
02	Issued for Minor Variance Application (Rev-1)	29/5/23	
01	Issued for Minor Variance Application	15/5/23	
NO.	DESCRIPTION	DATE	
	REVISIONS		





# ARRAY INTERNATIONAL ARCHITECTS INC.

250 Ferrand Dr. - Suite 410 T. 416-733-3583 E. info@arraygroup.com www.arraygroup.ca

### Swimming Pool and Cabana

148 Vla Teodoro, Vaughar

Site Plan


 A - 001

 Project 9:
 2022,15

 Date:
 29 June, 2023

 Towner By:
 AB

 Checked By:
 NED



#### NOTE:

The Contractor shall check all dimensions of the work and shall report discrepancies to the Architect before proceeding.

All drawings and specifications are the property of ARRAY INTERNATIONAL ARCHITECTS INC, which reserves its copyright with respect to this document. It shall not be duplicated, used or circulated for any other purpose than that for which it was lissued.

Written dimensions shall govern where they differ from scaled measurements. The Architect accepts no responsbillty for measurements scaled from the drawlngs.

The Architect is not responsible for the accuracy of survey, structural, mechanical, electrical, etc., information shown on this drawing. Refer to the appropriate consultant's drawings before proceeding with the work. Construction must conform to all applicable codes and requirements of authoritles having jurisdiction. The contractor working from drawings not specifically marked For Construction must assume full responsibility and bear costs for any corrections or damages resulting of sald work.

04	Issued for Minor Variance Application (Rev-4)	29/6/23
03	Issued for Minor Variance Application (Rev-2)	20/6/23
02	Issued for Minor Variance Application (Rev-1)	29/5/23
01	Issued for Minor Variance Application	15/5/23
NO.	DESCRIPTION	DATE

REVISIONS







ASSOCAL

# ARCHITECTS INC.

250 Ferrand Dr. – Sulte 410 T. 416-733-3583 E. info@arraygroup.com www.arraygroup.ca

# Swimming Pool and Cabana


148 Vla Teodoro, Vaughar

Nicolas Carci

Site Plan Variance plan

A - 002

t#:	2022.15
	29 June, 2023
By:	AB
ed By:	NED
	1:2













 02
 Issued for Minor Variance Application (Rev-1)
 29/5/2

 01
 Issued for Minor Variance Application
 15/5/2

REVISIONS

The Contractor shall check all dimensions of the work and shall report discrepancies to the Architect before proceeding. All drawings and specifications are the property o ARRAY INTERNATIONAL ARCHITECTS INC., which reserves its copyright with respect to this document. It shall not be duplicated, used or circulated for any other purpose than that for which

Written dimensions shall govern where they differ from scaled measurements. The Architect accepts o responsbillty for measurements scaled from th

The Architect is not responsible for the accuracy of survey, structural, mechanical, electrical, etc. information shown on this drawing. Refer to the appropriate consultant's drawings before proceeding with the work. Construction must

conform to all applicable codes and requirements of authorities having jurisdiction. The contractor working from drawings not specifically marked 'Fo Construction must assume full responsibility and bear costs for any corrections or damages

t was Issued.

esulting of sald work.

#### ARRAY INTERNATIONAL ARCHITECTS INC

250 Ferrand Dr. - Suite 410 T. 416-733-3583 E. info@arraygroup.com www.arraygroup.ca


### Swimming Pool and Cabana

148 Vla Teodoro, Vaughar

Cabana Plan

A - 003

:	2022.15
	29 June, 2023
y:	AB
By:	NED
	1-1



The Contractor shall check all dimensions of the work and shall report discrepancies to the Architect before proceeding.

All drawings and specifications are the property of ARRAY INTERNATIONAL ARCHITECTS INC., which reserves its copyright with respect to this document. It shall not be duplicated, used or circulated for any other purpose than that for which It was Issued.

Written dimensions shall govern where they differ from scaled measurements. The Architect accepts no responsbillty for measurements scaled from th drawings.

The Architect is not responsible for the accuracy of survey, structural, mechanical, electrical, etc., information shown on this drawing. Refer to the appropriate consultants drawing, select to the appropriate consultants drawings before proceeding with the work. Construction must conform to all applicable codes and requirements of authorities having jurisdiction. The contractor working from drawings not specifically marked For Construction must assume full responsibility and bear costs for any corrections or damages resulting of said work.

04	Issued for Minor Variance Application (Rev-3)	29/6/23	
03	Issued for Minor Variance Application (Rev-2)	20/6/23	
02	Issued for Minor Variance Application (Rev-1)	29/5/23	
01	Issued for Minor Variance Application	15/5/23	
NO.	DESCRIPTION	DATE	
	REVISIONS		







# 250 Ferrand Dr. - Suite 410 T. 416-733-3583 E. info@arraygroup.com www.arraygroup.ca

# Swimming Pool and Cabana

148 Vla Teodoro, Vaughar

Cabana Variance Section

A - 004

Project #:	2022.15
Date:	29 June, 2023
Drawn By:	AB
Checked By:	NED
Scale:	1:2

SCHEDULE B: STAFF & AGENCY COMMENTS					
DEPT/AGENCY	Circulated	Comments Received	Conditions	Nature of Comments	
TRCA *Schedule B	Х	X		General Comments	
Ministry of Transportation (MTO) *Schedule B				No Comments Received to Date	
Region of York *Schedule B	Х	Х		General Comments	
Alectra *Schedule B	Х	X		General Comments	
Bell Canada *Schedule B	Х			No Comments Received to Date	
YRDSB *Schedule B					
YCDSB *Schedule B					
CN Rail *Schedule B					
CP Rail *Schedule B					
TransCanada Pipeline *Schedule B	Х			No Comments Received to Date	
Metrolinx *Schedule B					
Propane Operator *Schedule B					
Development Planning	Х			Application Under Review	
Building Standards (Zoning)	Х	Х		General Comments	



**Date:** June 16<sup>th</sup> 2023

Attention: Christine Vigneault

**RE:** Request for Comments

File No.: A081-23

**Related Files:** 

**Applicant** Array International Architects Inc.

**Location** 148 Via Teodoro



# **COMMENTS:**

	We have reviewed the proposed Variance Application and have no comments or objections to its approval.
X	We have reviewed the proposed Variance Application and have no objections to its approval, subject to the following comments (attached below).
	We have reviewed the proposed Variance Application and have the following concerns (attached below).

Alectra Utilities (formerly PowerStream) has received and reviewed the proposed Variance Application. This review, however, does not imply any approval of the project or plan.

All proposed billboards, signs, and other structures associated with the project or plan must maintain minimum clearances to the existing overhead or underground electrical distribution system as specified by the applicable standards, codes and acts referenced.

In the event that construction commences, and the clearance between any component of the work/structure and the adjacent existing overhead and underground electrical distribution system violates the Occupational Health and Safety Act, the customer will be responsible for 100% of the costs associated with Alectra making the work area safe. All construction work will be required to stop until the safe limits of approach can be established.

In the event construction is completed, and the clearance between the constructed structure and the adjacent existing overhead and underground electrical distribution system violates the any of applicable standards, acts or codes referenced, the customer will be responsible for 100% of Alectra's cost for any relocation work.

## References:

- Ontario Electrical Safety Code, latest edition (Clearance of Conductors from Buildings)
- Ontario Health and Safety Act, latest edition (Construction Protection)
- Ontario Building Code, latest edition (Clearance to Buildings)
- PowerStream(Construction Standard 03-1, 03-4, 03-9), attached
- Canadian Standards Association, latest edition (Basic Clearances)

If more information is required, please contact either of the following:

Stephen Cranley, C.E.T Mitchell Penner

Supervisor, Distribution Design, ICI & Layouts (North)

Phone: 1-877-963-6900 ext. 31297

Supervisor, Distribution Design-Subdivisions


Phone: 416-302-6215

E-mail: stephen.cranley@alectrautilities.com

Email: Mitchell.Penner@alectrautilities.com



	SYSTEM VOLTAGE			
LOCATION OF WIRES, CABLES OR CONDUCTORS	SPAN GUYS AND COMMUNICATIONS WIRES		4.16/2.4kV TO 27.6/16kV (SEE NOTE 1)	44 <b>k</b> V
	MINIMUM VERTICAL CLEARANCES (SEE NOTE 2)			
OVER OR ALONGSIDE ROADS, DRIVEWAYS OR LANDS ACCESSIBLE TO <u>VEHICLES</u>	442cm	442cm	480cm	520cm
OVER GROUND ACCESSIBLE TO PEDESTRIANS AND BICYCLES ONLY 250cm		310cm	340cm	370cm
ABOVE TOP OF RAIL AT RAILWAY CROSSINGS	730cm	730cm	760cm	810cm



- MINIMUM ATTACHMENT HEIGHT = MAXIMUM SAG + MINIMUM VERTICAL CLEARANCE (FROM ABOVE TABLE)
  - GRADE DIFFERENCE

  - + 0.3m (VEHICLE OR RAILWAY LOCATION) + SNOW DEPTH (PEDESTRIAN LOCATION, SEE NOTE 3)

# NOTES:

- THE MULTIGROUNDED SYSTEM NEUTRAL HAS THE SAME CLEARANCE AS THE 600V SYSTEM.
- 2. THE VERTICAL CLEARANCES IN THE ABOVE TABLE ARE UNDER MAXIMUM SAG CONDITIONS.
- 3. REFER TO CSA STANDARD C22.3 No.1, ANNEX D FOR LOCAL SNOW DEPTH VALUES.
- 4. ALL CLEARANCES ARE IN ACCORDANCE TO CSA STANDARD C22.3.

REFERENCES				
SAGS	AND	TENSIONS	SECTION	02

METRIC

810cm

760cm 730cm

520cm

480cm

442cm 370cm

340cm

310cm 250cm IMPERIAL (APPROX)

27'-0" 25'-4"

24'-4" 17'-4"

16'-0' 15'-5

10'-4

8'-4

# MINIMUM VERTICAL CLEARANCES OF WIRES, CABLES AND CONDUCTORS ABOVE GROUND OR RAILS


ORIGINAL ISSUE DATE: 2010-DEC-24 REVISION NO: R1 REVISION DATE: 2012-JAN-09


Certificate of Approval This construction Standard meets the safety requirements of Section 4 of Regulation 22/04		
Joe Crozier, P.Eng. Name	2012-JAN-09 Date	
P.Eng. Approval By:	Joe Crozier	



# Construction Standard

03 - 4





VOLTAGE	MINIMUM HORIZONTAL CLEARNACE UNDER MAXIMUM SWING CONDITIONS DIMENSION "X" (SEE NOTES 1, 3 & 4)	MINIMUM VERTICAL CLEARANCE UNDER MAXIMUM DESIGN SAG CONDITIONS DIMENSION "Y" (SEE NOTES 1, 2, 4 & 5)
0-600V AND NEUTRAL	100cm	250cm
4.16/2.4 TO 44kV	300cm	480cm

- $\underline{\mathsf{NOTES}}$  under no circumstances shall a conductor be permitted to penetrate the envelope shown by the dotted line.
- THE VERTICAL CLEARANCES ARE UNDER CONDITIONS OF MAXIMUM DESIGN SAG.
- THE HORIZONTAL CLEARANCES ARE UNDER CONDITIONS OF MAXIMUM SWING. WHERE THE CONDUCTOR SWING IS NOT KNOWN A HORIZONTAL CLEARANCE OF 480CM SHALL BE USED.
- BUILDINGS THAT EXCEED 3 STOREYS OR 15M IN HEIGHT, THE MINIMUM HORIZONTAL CLEARANCE OF THE SECONDARY CONDUCTORS SHOULD BE INCREASED TO 300cm WHERE IT IS NECESSARY TO ALLOW FOR THE RAISING OF LADDERS BY LOCAL FIRE DEPARTMENTS.
- IN SITUATIONS SUCH AS MULTI-LEVEL GARAGES, WHERE ROOFS ARE NORMALLY USED BY PERSONS AND VEHICLES, THE VERTICAL CLEARANCES OF POWERSTREAM STANDARD 03-1SHALL APPLY.
- DISTRIBUTION LINES CONSTRUCTED NEAR BUILDINGS SHALL BE BUILT TO AVOID OVERHANG WHEREVER POSSIBLE. WHERE LINES MUST BE CONSTRUCTED OVER OR ADJACENT TO BUILDINGS THE APPLICABLE HORIZONTAL AND VERTICAL CLEARANCES SHALL BE AT CONDITIONS OF MAXIMUM CONDUCTOR SWING AND MAXIMUM SAG. THE ABOVE CLEARANCES ARE DESIGNED TO PREVENT PERSONS ON OR IN BUILDINGS AS WELL AS EXTERNAL MACHINERY USED IN CONJUCTION WITH A BUILDING TO COME IN CONTACT WITH CONDUCTORS, EFFORTS SHOULD BE MADE TO INCREASE THESE CLEARANCES WHERE POSSIBLE.
- 7. ALL CLEARANCES ARE IN ACCORDANCE TO CSA C22.3 NO.1-06 (TABLE-9).


CONVERSION TABLE		
METRIC	(APPROX)	
480cm	16'-0"	
300cm	10'-0"	
250cm	8'-4"	
10000	¥1_4**	

# MINIMUM VERTICAL & HORIZONTAL CLEARANCES OF CONDUCTORS FROM BUILDINGS OR OTHER PERMANENT STRUCTURES (CONDUCTORS NOT ATTACHED TO BUILDINGS)

Certificate of Approval This construction Standard meets the safety requirements of Section 4 of Regulation 22/04 Debbie Dadwani, P.Eng. P.Eng. Approval By: D. Dadwani

ORIGINAL ISSUE DATE: 2010—MAY—05 REVISION NO: REVISION DATE: PSSystem Plancho and Standards/Standard Design/PowerStream Standards/PowerStream Standards working (editor/Section 33-9/JWG 03-4 RD May 5, 2010, d V5/2010 8:22502 AM.





## NOTES:

- ANY STRUCTURE WITHIN 5.0 METRES OF POOL EDGE SHALL BE CONSIDERED PART OF THE POOL.
- THERE SHALL NOT BE ANY OVERHEAD SECONDARY OR COMMUNICATION WIRING (750V OR LESS) ABOVE THE POOL, AND ABOVE OTHER ELEVATED SURFACES ASSOCIATED WITH THE POOL, INCLUDING BUT NOT RESTRICTED TO A DIVING STRUCTURE, SLIDE, SWINGS, OBSERVATION STAND, TOWER OR PLATFORM, OR ABOVE THE ADJACENT AREA EXTENDING 5.0M HORIZONTALLY FROM THE POOL EDGE.
- 3. THERE SHALL NOT BE ANY OVERHEAD PRIMARY WIRING (751V -44KV) ABOVE THE POOL AND OTHER ELEVATED SURFACES ASSOCIATED WITH THE POOL, OR ABOVE THE ADJACENT AREA EXTENDING 7.5M HORIZONTALLY FROM THE POOL EDGE.
- 4. ANY UNDERGROUND CONDUCTORS SHALL BE 2.0M AWAY FROM POOL EDGE IN DUCT WITH NON-CONDUCTING JACKET. FOR DEPTH AND DUCT DETAILS REFER TO FIGURE 3 IN 25-100 FOR 200A SERVICE AND 25-101 FOR 400A SERVICE RESPECTIVELY, AS PER POWERSTREAM SERVICE DESIGN SPECIFICATIONS.
- 5. THESE DIMENSIONS APPLY TO ALL SIDES OF THE POOL.

MINIMUM CLEARANCES FOR
CONDUCTORS ADJACENT
TO SWIMMING POOLS

ORIGINAL ISSUE DATE: 2013-JUNE-12 REVISION NO: RO REVISION DATE:

CONVERSION TABLE		
METR <b>I</b> C	(APPROX.)	
7.5m	24'-6"	
5.0m	16'-3"	
2.0m	6'-6"	

REFERENCES		
FIGURE 3, 25-100	SECTION 25	
FIGURE 3, 25-101	SECTION 25	

Certificate of Approval This construction Standard meets the safety requirements of Section 4 of Regulation 22/04		
Joe Crozier, P.Eng. Name	2013-JUN-12 Date	
P.Eng. Approval By:	Joe Crozier	



To: Committee of Adjustment

From: Sarah Scauzillo, Building Standards Department

**Date:** June 30, 2023

**Applicant:** Array International Architects Inc.

**Location:** 148 Via Teodoro

PLAN 65M4136 Lot 74

**File No.(s):** A081/23

# Zoning Classification:

The subject lands are zoned R3(EN) and subject to the provisions of exception 14.919 under Zoning By-law 001-2021, as amended.

#	Zoning By-law 001-2021	Variance requested
1	A minimum rear yard setback of 2.4 metres to the proposed Residential Accessory Structure (Cabana) is required.	To permit a minimum rear yard setback of 0.5 metres to the prosed Residential Accessory Structure (Cabana).
2	A minimum interior side yard setback of 2.4 metres to the proposed Residential Accessory Structure (Cabana) is required.	To permit a minimum interior side yard setback of 0.5 metres to the proposed Residential Accessory Structure (Cabana).
3	A minimum distance of 0.6 metres shall be required from any permitted encroachment to the nearest lot line [Section 4.13]	To permit a minimum distance of 0.2 from the residential accessory structure eaves to the interior side lot line.
4	A minimum distance of 0.6 metres shall be required from any permitted encroachment to the nearest lot line [Section 4.13]	To permit a minimum distance of 0.2 from the residential accessory structure eaves to the rear lot line.
5	A minimum rear yard setback of 1.5 metres to the proposed pool is required [Section 4.21].	To permit a minimum rear yard setback of 0.9 metres to the proposed pool.
6	A minimum interior side yard setback of 1.5 metres to the proposed pool is required [Section 4.21].	To permit a minimum interior side yard setback of 1.0 metres to the proposed pool.
7	The maximum height of a residential accessory structure (Cabana) shall be 3.0 metres [Section 4.1.5].	To permit the maximum height of 3.42 metres for a residential accessory structure (Cabana).

# **Staff Comments:**

# **General Comments**

The applicant shall be advised that additional variances may be required upon review of detailed drawing for building permit/site plan approval.

# **Conditions of Approval:**

If the committee finds merit in the application, the following conditions of approval are recommended.

<sup>\*</sup> Comments are based on the review of documentation supplied with this application.

From: Kristen Regier

To: <u>Christine Vigneault; Committee of Adjustment; Lenore Providence</u>

Subject: [External] RE: A081/23 (148 Via Teodoro) - REQUEST FOR COMMENTS, CITY OF VAUGHAN

**Date:** Friday, June 16, 2023 11:54:07 AM

Attachments: <u>image001.png</u>

Hello,

The subject property is not located within TRCA's Regulated Area. TRCA's Planning and Regulatory policy interests are not impacted.

As such, TRCA has no comments on the application.

Best,

## Kristen Regier, MA (she / her)

Planner I

Development Planning and Permits | Development and Engineering Services Toronto and Region Conservation Authority (TRCA)

T: 437-880-2129

E: kristen.regier@trca.ca

A: 101 Exchange Avenue, Vaughan, ON, L4K 5R6 | trca.ca



From: Development Services
To: Christine Vigneault
Cc: Committee of Adjustment

Subject: [External] RE: A081/23 (148 Via Teodoro) - REQUEST FOR COMMENTS, CITY OF VAUGHAN

**Date:** Friday, June 16, 2023 5:40:35 PM

Attachments: image001.pnq

image003.png

Hi Christine,

The Regional Municipality of York has completed its review of the minor variance application – A081/23 and has no comment.

Many thanks,

Our working hours may be different. Please do not feel obligated to reply outside of your scheduled working hours. Let's work together to help foster healthy work-life boundaries.

**Niranjan Rajevan**, M.PI. | Associate Planner, Development Services, Planning and Economic Development, Corporate Services

The Regional Municipality of York | 17250 Yonge Street | Newmarket, ON L3Y 6Z1 1-877-464-9675 ext. 71521 | niranjan.rajevan@york.ca | www.york.ca

Our Values: Integrity, Commitment, Accountability, Respect, Excellence



Our Mission: Working together to serve our thriving communities - today and tomorrow

Please consider the environment before printing this email.

# SCHEDULE C: PUBLIC & APPLICANT CORRESPONDENCE

None