

ITEM: 6.2	COMMITTEE OF ADJUSTMENT REPORT SUMMARY MINOR VARIANCE APPLICATION FILE NUMBER A021/23 22 CROWN CRESCENT, WOODBRIDGE
------------------	--

**THIS REPORT CONTAINS COMMENTS FROM THE FOLLOWING
DEPARTMENTS & AGENCIES:**

*Please see **Schedule B** of this report for a copy of Development Planning and Agency correspondence.

Additional comments from departments and agencies may be received after the publication of the Staff Report. These comments will be processed as an addendum and posted on the City's Website.

DEPARTMENTS	Circulated	Comments Received	Conditions	Nature of Comments
Committee of Adjustment	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	General Comments
Building Standards (Zoning Review)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	General Comments
Building Inspection (Septic)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No Comments Received to Date
Development Planning	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Recommend Approval/No Conditions
Development Engineering	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Recommend Approval w/Conditions
Parks, Forestry and Horticulture Operations	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	General Comments
By-law & Compliance, Licensing & Permits	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No Comments Received to Date
Development Finance	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	General Comments
Real Estate	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Fire Department	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No Comments Received to Date
AGENCIES	Circulated	Comments Received	Conditions	Nature of Comments
TRCA	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	General Comments
Ministry of Transportation (MTO)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Region of York	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	General Comments
Alectra	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	General Comments
Bell Canada	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No Comments Received to Date
YRDSB	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
YCDSB	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
CN Rail	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
CP Rail	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
TransCanada Pipeline	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No Comments Received to Date
Metrolinx	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Propane Operator	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

PUBLIC & APPLICANT CORRESPONDENCE

*Please see **Schedule C** of this report for a copy of the public & applicant correspondence listed below.

The deadline to submit public comments is **noon on the last business day prior to the scheduled hearing date.**

Comments and written public submissions received after the publication of this Staff Report will be processed as an addendum and posted on the City's Website.

All personal information collected because of this public meeting (including both written and oral submissions) is collected under the authority of the Municipal Act, the Municipal Freedom of Information and Protection of Privacy Act (MFIPPA), the Planning Act and all other relevant legislation, and will be used to assist in deciding on this matter. All personal information (as defined by MFIPPA), including (but not limited to) names, addresses, opinions and comments collected will become property of the City of Vaughan, will be made available for public disclosure (including being posted on the internet) and will be used to assist the Committee of Adjustment and staff to process this application.

Correspondence Type	Name	Address	Date Received (mm/dd/yyyy)	Summary
None				

**PREVIOUS COA DECISIONS ON THE SUBJECT LAND SUBJECT TO ZONING
BY-LAW 001-2021**

*Please see **Schedule D** for a copy of the Decisions listed below

File Number	Date of Decision MM/DD/YYYY	Decision Outcome
None		

ADJOURNMENT HISTORY

* Previous hearing dates where this application was adjourned by the Committee and public notice issued.

None	
------	--



**COMMITTEE OF ADJUSTMENT REPORT
MINOR VARIANCE APPLICATION
A021/23
22 CROWN CR, WOODBRIDGE**

ITEM NUMBER: 6.2	CITY WARD #: 2
APPLICANT:	Diana Alvarado & Ramon Alvarado
AGENT:	Twain Warren
PROPERTY:	22 Crown Crescent, Woodbridge
ZONING DESIGNATION:	See below.
VAUGHAN OFFICIAL PLAN (2010) DESIGNATION:	Vaughan Official Plan 2010 ('VOP 2010'): "Low-Rise Residential"
RELATED DEVELOPMENT APPLICATIONS:	None
PURPOSE OF APPLICATION:	Relief from the Zoning By-law is being requested to permit a proposed swimming pool and an existing shed.

The following variances are being requested from the City's Zoning By-law to accommodate the above proposal:

The subject lands are zoned R3A(EN) – Third Density Residential Zone (Established Neighbourhood) under Zoning By-law 001-2021, as amended.

#	Zoning By-law 001-2021	Variance requested
1	The minimum setback of an outdoor swimming pool to any lot line shall be 1.5 m. The setback shall be measured from the inside wall of the outdoor swimming pool [Section 4.21.3].	To permit a minimum rear yard setback of 1.2 m to an outdoor swimming pool.
2	A residential accessory structure with a height greater than 2.8 metres shall not be located closer than 2.4 m to any lot line [Section 4.1.2.1 b.]	To permit a residential accessory structure with a height greater than 2.8 metres to be located 0.34 metres to the interior side lot line.
3	A residential accessory structure with a height greater than 2.8 metres shall not be located closer than 2.4 m to any lot line [Section 4.1.2.1 b.].	To permit a residential accessory structure with a height greater than 2.8 metres to be located 0.48 metres to the rear lot line.
4	In any residential zone, the maximum height of an accessory building and residential accessory structure shall be 3.0 m [Section 4.1.4.1].	To permit a maximum height of 3.28 m for a residential accessory structure.
5	Unless otherwise expressly permitted by this By-law, a minimum distance of 0.6 m shall be required from any permitted encroachment to the nearest lot line [Section 4.13.3].	To permit eaves and gutters to encroach up to 0.19 m to the interior side lot line.
6	Unless otherwise expressly permitted by this By-law, a minimum distance of 0.6 m shall be required from any permitted encroachment to the nearest lot line [Section 4.13.3].	To permit eaves and gutters to encroach up to 0.38 metres to the rear lot line.

HEARING INFORMATION

DATE OF MEETING: Thursday, October 19, 2023
TIME: 6:00 p.m.
MEETING LOCATION: Vaughan City Hall, Woodbridge Room (2nd Floor), 2141 Major Mackenzie Drive
LIVE STREAM LINK: Vaughan.ca/LiveCouncil

PUBLIC PARTICIPATION

HEARING INFORMATION

If you would like to speak to the Committee of Adjustment at the meeting, either remotely or in person, please complete the [Request to Speak Form](#) and submit to cofa@vaughan.ca

If you would like to submit written comments, please quote file number above and submit by mail or email to:

Email: cofa@vaughan.ca

Mail: City of Vaughan, Office of the City Clerk, Committee of Adjustment, 2141 Major Mackenzie Drive, Vaughan, ON, L6A 1T1

To speak electronically, pre-registration is required by completing the [Request to Speak Form](#) on-line and submitting it to cofa@vaughan.ca no later than NOON on the last business day before the meeting.

THE DEADLINE TO REGISTER TO SPEAK ELECTRONICALLY OR SUBMIT WRITTEN COMMENTS ON THE ABOVE NOTED FILE(S) IS NOON ON THE LAST BUSINESS DAY BEFORE THE MEETING.

INTRODUCTION

Staff and Agencies act as advisory bodies to the Committee of Adjustment. The comments contained in this report are presented as recommendations to the Committee.

Section 45(1) of the Planning Act sets the criteria for authorizing minor variances to the City of Vaughan's Zoning By-law. Accordingly, review of the application may consider the following:

- That the general intent and purpose of the by-law will be maintained.
- That the general intent and purpose of the official plan will be maintained.
- That the requested variance(s) is/are acceptable for the appropriate development of the subject lands.
- That the requested variance(s) is/are minor in nature.

Public written and oral submissions relating to this application are taken into consideration by the Committee of Adjustment as part of its deliberations and final decision on this matter.

COMMITTEE OF ADJUSTMENT COMMENTS

Date Public Notice Mailed:	October 5, 2023	
Date Applicant Confirmed Posting of Sign:	October 2, 2023	
Applicant Justification for Variances: <small>*As provided by Applicant in Application Form</small>	Purpose of the application is after meeting city inspector, required to apply for minor variance for pool setback of 1.2 m in one area (all other areas are 1.5m or more) as shown in attached plan.	
Adjournment Requests (from staff): <small>*Adjournment requests provided to applicant prior to issuance of public notice</small>	None	
Was a Zoning Review Waiver (ZRW) Form submitted by Applicant: <small>*ZRW Form may be used by applicant in instances where a revised submission is made, and zoning staff do not have an opportunity to review and confirm variances prior to the issuance of public notice. *A revised submission may be required to address staff / agency comments received as part of the application review process. *Where a zoning review has not been completed on a revised submission, an opportunity is provided to the applicant to adjourn the proposal prior to the issuance of public notice.</small>	No	
Adjournment Fees: In accordance with Procedural By-law 069-2019, an Adjournment Fee is applicable to reschedule an application after the issuance of public notice where a request for adjournment has been provided to the applicant prior to the issuance of public notice. An Adjournment Fee can only be waived in instances where adjournment of an application is requested by the Committee or staff after the issuance of public notice.		
Committee of Adjustment Comments:	None	
Committee of Adjustment Recommended Conditions of Approval:	None	

BUILDING STANDARDS (ZONING) COMMENTS

****See Schedule B for Building Standards (Zoning) Comments**

BUILDING STANDARDS (ZONING) COMMENTS

Building Standards Recommended Conditions of Approval:	None
---	------

DEVELOPMENT PLANNING COMMENTS

**See Schedule B for Development Planning Comments.

Development Planning Recommended Conditions of Approval:	None
---	------

DEVELOPMENT ENGINEERING COMMENTS

[Link to Grading Permit](#) [Link to Pool Permit](#) [Link to Curb Curt Permit](#) [Link Culvert Installation](#)

Due to the size of the proposed cabana on the subject property, which measures 21.64 m², the Owner/Applicant must acquire a Lot Grading Permit from the Development Inspection and Lot Grading Division of the City's Development Engineering Department. It's important note that any in-ground structure exceeding 10 m² necessitates a Grading Permit. Once the Grading Permit is obtained, please reach out to the Development Engineering Reviewer to clear the Condition imposed on this application.

The Owner/Applicant's proposed work involves increasing the Lot Coverage on the subject property. This addition of hardscape could potentially affect the City's Storm Water management system. Development Engineering highly recommends that the Owner/Applicant incorporate Low-Impact Development (LID) measures, such as bioswales, permeable pavers, rain gardens, rain barrels, etc., to minimize the impact on the stormwater system. If additional information is needed, please reach out to the Development Engineering COA reviewer.

The Development Engineering Department does not object to the Minor Variance application A021/23, subject to the following condition(s):

Development Engineering Recommended Conditions of Approval:	The Owner/Applicant shall submit the final Lot Grading and/or Servicing Plan to the Development Inspection and Lot Grading Division within the City's Development Engineering Department before initiating any work on the property. To apply for a Grading Permit, please visit the Permit page on the City of Vaughan website. For any inquiries regarding the Grading Permit, please feel free to contact the Development Engineering Department via email at DEPermits@vaughan.ca .
--	---

PARKS, FORESTRY & HORTICULTURE (PFH) COMMENTS

Forestry has no comment at this time.

PFH Recommended Conditions of Approval:	None
--	------

DEVELOPMENT FINANCE COMMENTS

No comment no concerns

Development Finance Recommended Conditions of Approval:	None
--	------

BY-LAW AND COMPLIANCE, LICENSING AND PERMIT SERVICES COMMENTS

No objection or comment

BCLPS Recommended Conditions of Approval:	None
--	------

BUILDING INSPECTION (SEPTIC) COMMENTS

No comments received to date.

Building Inspection Recommended Conditions of Approval:	None
--	------

FIRE DEPARTMENT COMMENTS

No comments received to date.

Fire Department Recommended Conditions of Approval:	None
--	------

SCHEDULES TO STAFF REPORT

*See Schedule for list of correspondence

Schedule A	Drawings & Plans Submitted with the Application
Schedule B	Staff & Agency Comments
Schedule C (if required)	Correspondence (Received from Public & Applicant)
Schedule D (if required)	Previous COA Decisions on the Subject Land

Should the Committee find it appropriate to approve this application in accordance with request and the sketch submitted with the application, as required by Ontario Regulation 200/96, the following conditions have been recommended:

SUMMARY OF RECOMMENDED CONDITIONS OF APPROVAL

All conditions of approval, unless otherwise stated, are considered to be incorporated into the approval “if required”. If a condition is no longer required after an approval is final and binding, the condition may be waived by the respective department or agency requesting conditional approval. A condition cannot be waived without written consent from the respective department or agency.

#	DEPARTMENT / AGENCY	CONDITION(S) DESCRIPTION
1	Development Engineering Rex.bondad@vaughan.ca	The Owner/Applicant shall submit the final Lot Grading and/or Servicing Plan to the Development Inspection and Lot Grading Division within the City's Development Engineering Department before initiating any work on the property. To apply for a Grading Permit, please visit the Permit page on the City of Vaughan website. For any inquiries regarding the Grading Permit, please feel free to contact the Development Engineering Department via email at DEPermits@vaughan.ca .

IMPORTANT INFORMATION – PLEASE READ

CONDITIONS: It is the responsibility of the owner/applicant and/or authorized agent to obtain and provide a clearance letter from respective department and/or agency (**see condition chart above for contact**). This letter must be provided to the Secretary-Treasurer to be finalized. All conditions must be cleared prior to the issuance of a Building Permit.

APPROVALS: Making any changes to your proposal after a decision has been made may impact the validity of the Committee’s decision.

An approval obtained from the Committee of Adjustment, where applicable, is tied to the building envelope shown on the plans and drawings submitted with the application and subject to the variance approval.

A building envelope is defined by the setbacks of the buildings and/or structures shown on the plans and drawings submitted with the application, as required by Ontario Regulation 200/96. Future development outside of an approved building envelope, where a minor variance was obtained, must comply with the provisions of the City’s Zoning By-law.

Elevation drawings are provided to reflect the style of roof (i.e. flat, mansard, gable etc.) to which a building height variance has been applied. Where a height variance is approved, building height is applied to the style of roof (as defined in the City’s Zoning By-law) shown on the elevation plans submitted with the application.

Architectural design features that are not regulated by the City’s Zoning By-law are not to be considered part of an approval unless specified in the Committee’s decision.

DEVELOPMENT CHARGES: That the payment of the Regional Development Charge, if required, is payable to the City of Vaughan before issuance of a building permit in accordance with the Development Charges Act and the Regional Development Charges By-law in effect at the time of payment.

That the payment of the City Development Charge, if required, is payable to the City of Vaughan before issuance of a building permit in accordance with the Development Charges Act and the City's Development Charges By-law in effect at the time of payment.

That the payment of the Education Development Charge if required, is payable to the City of Vaughan before issuance of a building permit in accordance with the Development Charges Act and the Boards of Education By-laws in effect at the time of payment

That the payment of Special Area Development charge, if required, is payable to the City of Vaughan before issuance of a building permit in accordance with the Development Charges Act and The City's


IMPORTANT INFORMATION – PLEASE READ

Development Charge By-law in effect at the time of Building permit issuance to the satisfaction of the Reserves/Capital Department.

NOTICE OF DECISION: If you wish to be notified of the decision in respect to this application or a related Ontario Land Tribunal (OLT) hearing you must complete a Request for Decision form and submit to the Secretary Treasurer (ask staff for details). In the absence of a written request to be notified of the Committee's decision you will **not** receive notice.


SCHEDULE A: DRAWINGS & PLANS

22 CROWN CRESCENT, WOODBRIDGE



DRAWING INFORMATION:

PRINT ON 11 X17



SCALE IN METERS

22 Crown Crescent Woodbridge, ON L4H 1S5			
client:		date:	revision:
scale:	1:125	2023-09-12	5
drawn by:	R.T	checked by:	R.T
		drawing #:	GRA - 1


**GRADING IN METRIC
USING DOOR SILL (100.00) AS BENCHMARK
BOX INDICATES PROPOSED GRADES**

- STANDARD DRAWING NOTES:**
- 1.1 Roof drains to discharge at front of dwelling units onto grassed areas via concrete splash pads and not conflict with walkways
 - 1.2 The contractor shall check and verify all given grade elevations prior to commencement of construction. Footings to bear on natural undisturbed soil or rock and to be a minimum of 1.22m below finished grade.
 - 1.3 All front and rear yards shall be graded at 2% to 5% grade within 6.0m of the dwelling unit.
 - 1.4 Maximum driveway slope shall be 8%.
 - 1.5 The maximum allowable slope is 3:1 (horizontal to vertical) with a maximum elevation difference of 600mm.
 - 1.6 Driveways to be set back a minimum of 1.0m, from above ground services or other obstruction.

PLANS PREPARED BY APPLICANT


RECEIVED
By attwalap at 12:07 pm, Sep 13, 2023

A021/23



#	Zoning By-law 001-2021	Variance requested
1	The minimum setback of an outdoor swimming pool to any lot line shall be 1.5 m. The setback shall be measured from the inside wall of the outdoor swimming pool [Section 4.21.3].	To permit a minimum rear yard setback of 1.2 m to an outdoor swimming pool.
2	A residential accessory structure with a height greater than 2.8 metres shall not be located closer than 2.4 m to any lot line [Section 4.1.2.1 b].	To permit a residential accessory structure with a height greater than 2.8 metres to be located 0.34 metres to the interior side lot line.
3	A residential accessory structure with a height greater than 2.8 metres shall not be located closer than 2.4 m to any lot line [Section 4.1.2.1 b].	To permit a residential accessory structure with a height greater than 2.8 metres to be located 0.48 metres to the rear lot line.
4	In any residential zone, the maximum height of an accessory building and residential accessory structure shall be 3.0 m [Section 4.1.4.1].	To permit a maximum height of 3.28 m for a residential accessory structure.
5	Unless otherwise expressly permitted by this By-law, a minimum distance of 0.6 m shall be required from any permitted encroachment to the nearest lot line [Section 4.13.3].	To permit eaves and gutters to encroach up to 0.19 m to the interior side lot line.
6	Unless otherwise expressly permitted by this By-law, a minimum distance of 0.6 m shall be required from any permitted encroachment to the nearest lot line [Section 4.13.3].	To permit eaves and gutters to encroach up to 0.38 metres to the rear lot line.

Received
June 27, 2023



SLOPED ROOF 24 inches (D.b.m)

FRONT HEIGHT: 10 feet 5 inches (3.2m)


BACK HEIGHT: 8 feet 5 inches (2.6m)

MEAN HEIGHT: 9 feet 2.5 inches (2.8m)

FRONT WIDTH: 19 feet 5 inches (5.9m)
SIDE WIDTH: 12 feet (3.66m)

A021/23

RECEIVED
By Christine Vigneault at 4:56 pm, Aug 16, 2023



FRONT HEIGHT: 10 feet 5 inches (3.2 m)
 BACK HEIGHT: 8 feet 5 inches (2.6 m)
 MEAN HEIGHT: 9 feet 2.5 inches (2.8 m)


FRONT WIDTH: 19 feet 5 inches (5.9 m)
 SIDE WIDTH: 12 feet (3.66 m)

Received

June 13, 2023

A071/23

Backyard Shed Dimensions



SCHEDULE B: STAFF & AGENCY COMMENTS

DEPT/AGENCY	Circulated	Comments Received	Conditions	Nature of Comments
TRCA *Schedule B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	General Comments
Ministry of Transportation (MTO) *Schedule B	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Region of York *Schedule B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	General Comments
Alectra *Schedule B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	General Comments
Bell Canada *Schedule B	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No Comments Received to Date
YRDSB *Schedule B	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
YCDSB *Schedule B	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
CN Rail *Schedule B	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
CP Rail *Schedule B	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
TransCanada Pipeline *Schedule B	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No Comments Received to Date
Metrolinx *Schedule B	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Propane Operator *Schedule B	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Development Planning	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Recommend Approval/no conditions
Building Standards (Zoning)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	General Comments

Date: July 20th 2023

Attention: **Christine Vigneault**

RE: Request for Comments

File No.: **A021-23**

Related Files:

Applicant Ramon & Diana Alavardo

Location 22 Crown Crescent

COMMENTS:

- We have reviewed the proposed Variance Application and have no comments or objections to its approval.
- We have reviewed the proposed Variance Application and have no objections to its approval, subject to the following comments (attached below).
- We have reviewed the proposed Variance Application and have the following concerns (attached below).

Alectra Utilities (formerly PowerStream) has received and reviewed the proposed Variance Application. This review, however, does not imply any approval of the project or plan.

All proposed billboards, signs, and other structures associated with the project or plan must maintain minimum clearances to the existing overhead or underground electrical distribution system as specified by the applicable standards, codes and acts referenced.

In the event that construction commences, and the clearance between any component of the work/structure and the adjacent existing overhead and underground electrical distribution system violates the Occupational Health and Safety Act, the customer will be responsible for 100% of the costs associated with Alectra making the work area safe. All construction work will be required to stop until the safe limits of approach can be established.

In the event construction is completed, and the clearance between the constructed structure and the adjacent existing overhead and underground electrical distribution system violates the any of applicable standards, acts or codes referenced, the customer will be responsible for 100% of Alectra's cost for any relocation work.

References:

- Ontario Electrical Safety Code, latest edition (Clearance of Conductors from Buildings)
- Ontario Health and Safety Act, latest edition (Construction Protection)
- Ontario Building Code, latest edition (Clearance to Buildings)
- PowerStream(Construction Standard 03-1, 03-4, 03-9), attached
- Canadian Standards Association, latest edition (Basic Clearances)

If more information is required, please contact either of the following:

Stephen Cranley, C.E.T

Mitchell Penner


Supervisor, Distribution Design, ICI & Layouts (North)
Phone: 1-877-963-6900 ext. 31297

Supervisor, Distribution Design-Subdivisions
Phone: 416-302-6215

E-mail: stephen.cranley@alecrautilities.com

Email: Mitchell.Penner@alecrautilities.com

LOCATION OF WIRES, CABLES OR CONDUCTORS	SYSTEM VOLTAGE			
	SPAN GUYS AND COMMUNICATIONS WIRES	UP TO 600V AND NEUTRAL	4.16/2.4kV TO 27.6/16kV (SEE NOTE 1)	44kV
	MINIMUM VERTICAL CLEARANCES (SEE NOTE 2)			
OVER OR ALONGSIDE ROADS, DRIVEWAYS OR LANDS ACCESSIBLE TO VEHICLES	442cm	442cm	480cm	520cm
OVER GROUND ACCESSIBLE TO PEDESTRIANS AND BICYCLES ONLY	250cm	310cm	340cm	370cm
ABOVE TOP OF RAIL AT RAILWAY CROSSINGS	730cm	730cm	760cm	810cm



MINIMUM ATTACHMENT HEIGHT = MAXIMUM SAG
 + MINIMUM VERTICAL CLEARANCE (FROM ABOVE TABLE)
 ± GRADE DIFFERENCE
 + 0.3m (VEHICLE OR RAILWAY LOCATION)
 + SNOW DEPTH (PEDESTRIAN LOCATION, SEE NOTE 3)

NOTES:

1. THE MULTIGROUNDED SYSTEM NEUTRAL HAS THE SAME CLEARANCE AS THE 600V SYSTEM.
2. THE VERTICAL CLEARANCES IN THE ABOVE TABLE ARE UNDER MAXIMUM SAG CONDITIONS.
3. REFER TO CSA STANDARD C22.3 No.1, ANNEX D FOR LOCAL SNOW DEPTH VALUES.
4. ALL CLEARANCES ARE IN ACCORDANCE TO CSA STANDARD C22.3.

CONVERSION TABLE

METRIC	IMPERIAL (APPROX)
810cm	27'-0"
760cm	25'-4"
730cm	24'-4"
520cm	17'-4"
480cm	16'-0"
442cm	15'-5"
370cm	12'-4"
340cm	11'-4"
310cm	10'-4"
250cm	8'-4"

REFERENCES

SAGS AND TENSIONS | SECTION 02


MINIMUM VERTICAL CLEARANCES OF WIRES, CABLES AND CONDUCTORS ABOVE GROUND OR RAILS

ORIGINAL ISSUE DATE: 2010-DEC-24 REVISION NO: R1 REVISION DATE: 2012-JAN-09

Certificate of Approval

This construction Standard meets the safety requirements of Section 4 of Regulation 22/04

Joe Crozier, P.Eng. 2012-JAN-09
 Name Date
 P.Eng. Approval By: Joe Crozier



VOLTAGE	MINIMUM HORIZONTAL CLEARNACE UNDER MAXIMUM SWING CONDITIONS DIMENSION "X" (SEE NOTES 1, 3 & 4)	MINIMUM VERTICAL CLEARANCE UNDER MAXIMUM DESIGN SAG CONDITIONS DIMENSION "Y" (SEE NOTES 1, 2, 4 & 5)
0-600V AND NEUTRAL	100cm	250cm
4.16/2.4 TO 44kV	300cm	480cm

NOTES


1. UNDER NO CIRCUMSTANCES SHALL A CONDUCTOR BE PERMITTED TO PENETRATE THE ENVELOPE SHOWN BY THE DOTTED LINE.
2. THE VERTICAL CLEARANCES ARE UNDER CONDITIONS OF MAXIMUM DESIGN SAG.
3. THE HORIZONTAL CLEARANCES ARE UNDER CONDITIONS OF MAXIMUM SWING. WHERE THE CONDUCTOR SWING IS NOT KNOWN A HORIZONTAL CLEARANCE OF 480CM SHALL BE USED.
4. BUILDINGS THAT EXCEED 3 STOREYS OR 15M IN HEIGHT, THE MINIMUM HORIZONTAL CLEARANCE OF THE SECONDARY CONDUCTORS SHOULD BE INCREASED TO 300cm WHERE IT IS NECESSARY TO ALLOW FOR THE RAISING OF LADDERS BY LOCAL FIRE DEPARTMENTS.
5. IN SITUATIONS SUCH AS MULTI-LEVEL GARAGES, WHERE ROOFS ARE NORMALLY USED BY PERSONS AND VEHICLES, THE VERTICAL CLEARANCES OF POWERSTREAM STANDARD 03-1 SHALL APPLY.
6. DISTRIBUTION LINES CONSTRUCTED NEAR BUILDINGS SHALL BE BUILT TO AVOID OVERHANG WHEREVER POSSIBLE. WHERE LINES MUST BE CONSTRUCTED OVER OR ADJACENT TO BUILDINGS THE APPLICABLE HORIZONTAL AND VERTICAL CLEARANCES SHALL BE AT CONDITIONS OF MAXIMUM CONDUCTOR SWING AND MAXIMUM SAG. THE ABOVE CLEARANCES ARE DESIGNED TO PREVENT PERSONS ON OR IN BUILDINGS AS WELL AS EXTERNAL MACHINERY USED IN CONJUNCTION WITH A BUILDING TO COME IN CONTACT WITH CONDUCTORS. EFFORTS SHOULD BE MADE TO INCREASE THESE CLEARANCES WHERE POSSIBLE.
7. ALL CLEARANCES ARE IN ACCORDANCE TO CSA C22.3 NO.1-06 (TABLE-9).

METRIC	IMPERIAL (APPROX)
480cm	16'-0"
300cm	10'-0"
250cm	8'-4"
100cm	3'-4"

MINIMUM VERTICAL & HORIZONTAL CLEARANCES OF CONDUCTORS FROM BUILDINGS OR OTHER PERMANENT STRUCTURES (CONDUCTORS NOT ATTACHED TO BUILDINGS)

Certificate of Approval
This construction Standard meets the safety requirements of Section 4 of Regulation 22/04
Debbie Dadwani, P.Eng. 2010-MAY-05
Name Date
P.Eng. Approval By: D. Dadwani

ORIGINAL ISSUE DATE: 2010-MAY-05 REVISION NO: REVISION DATE:
PS\System Planning and Standards\Standard Design\PowerStream Standards\PowerStream Standards working folder\Section 23-4\DWG 03-4 R0 May 5, 2010.dwg, 5/5/2010 9:22:02 AM, Adobe PDF



NOTES:

1. ANY STRUCTURE WITHIN 5.0 METRES OF POOL EDGE SHALL BE CONSIDERED PART OF THE POOL.
2. THERE SHALL NOT BE ANY OVERHEAD SECONDARY OR COMMUNICATION WIRING (750V OR LESS) ABOVE THE POOL, AND ABOVE OTHER ELEVATED SURFACES ASSOCIATED WITH THE POOL, INCLUDING BUT NOT RESTRICTED TO A DIVING STRUCTURE, SLIDE, SWINGS, OBSERVATION STAND, TOWER OR PLATFORM, OR ABOVE THE ADJACENT AREA EXTENDING 5.0M HORIZONTALLY FROM THE POOL EDGE.
3. THERE SHALL NOT BE ANY OVERHEAD PRIMARY WIRING (751V - 44KV) ABOVE THE POOL AND OTHER ELEVATED SURFACES ASSOCIATED WITH THE POOL, OR ABOVE THE ADJACENT AREA EXTENDING 7.5M HORIZONTALLY FROM THE POOL EDGE.
4. ANY UNDERGROUND CONDUCTORS SHALL BE 2.0M AWAY FROM POOL EDGE IN DUCT WITH NON-CONDUCTING JACKET. FOR DEPTH AND DUCT DETAILS REFER TO FIGURE 3 IN 25-100 FOR 200A SERVICE AND 25-101 FOR 400A SERVICE RESPECTIVELY, AS PER POWERSTREAM SERVICE DESIGN SPECIFICATIONS.
5. THESE DIMENSIONS APPLY TO ALL SIDES OF THE POOL.

CONVERSION TABLE	
METRIC	IMPERIAL (APPROX.)
7.5m	24'-6"
5.0m	16'-3"
2.0m	6'-6"

REFERENCES	
FIGURE 3, 25-100	SECTION 25
FIGURE 3, 25-101	SECTION 25

MINIMUM CLEARANCES FOR CONDUCTORS ADJACENT TO SWIMMING POOLS

ORIGINAL ISSUE DATE: 2013-JUNE-12 REVISION NO: R0 REVISION DATE:

Certificate of Approval	
This construction Standard meets the safety requirements of Section 4 of Regulation 22/04	
Joe Crozier, P.Eng.	2013-JUN-12
Name	Date
P.Eng. Approval By:	Joe Crozier

To: Committee of Adjustment
From: Lindsay Haviland, Building Standards Department
Date: August 17, 2023
Applicant: Ramon & Diana Alavardo
Location: 22 Crown Crescent
 PLAN 65M3289 Lot 89
File No.(s): A021/23

Zoning Classification:

The subject lands are zoned R3A(EN) – Third Density Residential Zone (Established Neighbourhood) under Zoning By-law 001-2021, as amended.

#	Zoning By-law 001-2021	Variance requested
1	The minimum setback of an outdoor swimming pool to any lot line shall be 1.5 m. The setback shall be measured from the inside wall of the outdoor swimming pool [Section 4.21.3].	To permit a minimum rear yard setback of 1.2 m to an outdoor swimming pool.
2	A residential accessory structure with a height greater than 2.8 metres shall not be located closer than 2.4 m to any lot line [Section 4.1.2.1 b.].	To permit a residential accessory structure with a height greater than 2.8 metres to be located 0.34 metres to the interior side lot line.
3	A residential accessory structure with a height greater than 2.8 metres shall not be located closer than 2.4 m to any lot line [Section 4.1.2.1 b.].	To permit a residential accessory structure with a height greater than 2.8 metres to be located 0.48 metres to the rear lot line.
4	In any residential zone, the maximum height of an accessory building and residential accessory structure shall be 3.0 m [Section 4.1.4.1].	To permit a maximum height of 3.28 m for a residential accessory structure.
5	Unless otherwise expressly permitted by this By-law, a minimum distance of 0.6 m shall be required from any permitted encroachment to the nearest lot line [Section 4.13.3].	To permit eaves and gutters to encroach up to 0.19 m to the interior side lot line.
6	Unless otherwise expressly permitted by this By-law, a minimum distance of 0.6 m shall be required from any permitted encroachment to the nearest lot line [Section 4.13.3].	To permit eaves and gutters to encroach up to 0.38 metres to the rear lot line.

Staff Comments:

Stop Work Order(s) and Order(s) to Comply:

There are no outstanding Orders on file

Building Permit(s) Issued:

A Building Permit has not been issued. The Ontario Building Code requires a building permit for structures that exceed 10m²

Other Comments:

General Comments	
1	The applicant shall be advised that additional variances may be required upon review of detailed drawing for building permit/site plan approval.
2	The height of the residential accessory structure shall be measured in accordance with the definitions in section 3.0 DEFINITIONS of By-Law 001-2021 as amended. Established grade shall be the approved grading at the time of the original building permit for the principal dwelling.

Conditions of Approval:

If the committee finds merit in the application, the following conditions of approval are recommended.

* Comments are based on the review of documentation supplied with this application.

To: Christine Vigneault, Committee of Adjustment Secretary Treasurer
From: Nancy Tuckett, Director of Development Planning
Date: October 11, 2023
Name of Owners: Ramon and Diana Alvarado
Location: 22 Crown Crescent
File No.(s): A021/23

Proposed Variance(s) (By-law 001-2021):

1. To permit a minimum rear yard setback of 1.2 m to an outdoor swimming pool.
2. To permit a residential accessory structure with a height greater than 2.8 m to be located 0.34 m to the interior side lot line.
3. To permit a residential accessory structure with a height greater than 2.8 m to be located 0.48 m to the rear lot line.
4. To permit a maximum height of 3.28 m for a residential accessory structure.
5. To permit eaves and gutters to encroach up to 0.19 m to the interior side lot line.
6. To permit eaves and gutters to encroach up to 0.38 m to the rear lot line.

By-Law Requirement(s) (By-law 001-2021):

1. The minimum setback of an outdoor swimming pool to any lot line shall be 1.5 m. The setback shall be measured from the inside wall of the outdoor swimming pool.
2. A residential accessory structure with a height greater than 2.8 m shall not be located closer than 2.4 m to any lot line.
3. A residential accessory structure with a height greater than 2.8 m shall not be located closer than 2.4 m to any lot line.
4. In any residential zone, the maximum height of an accessory building and residential accessory structure shall be 3.0 m.
5. Unless otherwise expressly permitted by this By-law, a minimum distance of 0.6 m shall be required from any permitted encroachment to the nearest lot line.
6. Unless otherwise expressly permitted by this By-law, a minimum distance of 0.6 m shall be required from any permitted encroachment to the nearest lot line.

Official Plan:

City of Vaughan Official Plan 2010 ('VOP 2010'): "Low-Rise Residential"

Comments:

The Owners are requesting relief to permit the existing pool and shed, with the above-noted variances.

The Development Planning Department has no objection to Variance 1 for the pool as the reduction to the rear yard setback is minor in nature, will only be fully utilized by a corner of the pool due to the angled rear lot line, and is not anticipated to be perceptible. The pool also complies with the interior side yard setback requirements in the Zoning By-law and maintains an appropriate area for safe access and maintenance.

The Development Planning Department has no objection to Variances 2, 3, and 4 for the residential accessory structure. The structure is modest in footprint and has a slanted roof that is lowest along the western side, facing the rear lot line. The proposed 3.28 m height is measured from the established grade to the highest roof edge, which faces the interior of the lot. The height of the structure when measured from the shorter roof edge is approximately 2.68 m. This results in a lower wall face fronting the neighbouring property to the rear, further mitigating the mass of the structure. Due to its modest footprint and the slanted roof design, the reduced interior side and rear yard setbacks are not anticipated to have adverse impacts to the neighbouring properties. The interior side and rear yard setbacks are also measured at pinch points and expand to 0.54 m and 0.75 m respectively, at their greatest extent. The Development Engineering Department has also reviewed the proposal and is satisfied that drainage in the rear yard will be maintained. As such, the structure is not anticipated to pose adverse use or

massing impacts to the neighbouring properties and an appropriate area for maintenance access is maintained.

The Development Planning Department has no objection to Variances 5 and 6 for the encroachment of the eaves and gutters. The setback for the eaves to the interior side lot line is not anticipated to pose adverse massing impacts due to the modest size of the shed and the encroachment being measured at the pinch point between the interior side lot line and the structure. The setback for the gutter to the rear lot line is also measured to the pinch point between the rear lot line and structure. As such, the increase to the eaves and gutter encroachments are minor in nature and no adverse massing impacts are anticipated to the neighbouring properties.

Accordingly, the Development Planning Department can support the requested variances and is of the opinion that the proposal is minor in nature, maintains the general intent and purpose of the Official Plan and Zoning By-law, and is desirable for the appropriate development of the land.

Recommendation:

The Development Planning Department recommends approval of the application.

Conditions of Approval:

If the Committee finds merit in the application, the following conditions of approval are recommended:

None

Comments Prepared by:

Joshua Cipolletta, Planner
David Harding, Senior Planner

From: [Kristen Regier](#)
To: [Committee of Adjustment](#)
Cc: [Christine Vigneault](#)
Subject: [External] RE: A021/23 (22 Crown Crescent) – REQUEST FOR COMMENTS, CITY OF VAUGHAN
Date: Thursday, July 20, 2023 11:25:44 AM
Attachments: [image001.png](#)

Hello,

The subject property at 22 Crown Crescent, Vaughan is not located within TRCA's Regulated Area. TRCA's Planning and Regulatory policy interests are not impacted.

As such, TRCA has no comments on the application.

Best,

Kristen Regier, MA (she / her)

Planner I

Development Planning and Permits | Development and Engineering Services

Toronto and Region Conservation Authority (TRCA)

T: [437-880-2129](tel:437-880-2129)

E: kristen.regier@trca.ca

A: [101 Exchange Avenue, Vaughan, ON, L4K 5R6](#) | trca.ca



Lenore Providence

From: Development Services <developmentservices@york.ca>
Sent: July-26-23 3:43 PM
To: Christine Vigneault
Cc: Committee of Adjustment
Subject: [External] RE: A021/23 (22 Crown Crescent) – REQUEST FOR COMMENTS, CITY OF VAUGHAN

Hi Christine,

The Regional Municipality of York has completed its review of the revised minor variance application – A021/23 and has no comment.

Many thanks,

Our working hours may be different. Please do not feel obligated to reply outside of your scheduled working hours. Let's work together to help foster healthy work-life boundaries.

Niranjan Rajevan, M.Pl. | Associate Planner, Development Services, Planning and Economic Development, Corporate Services

The Regional Municipality of York | 17250 Yonge Street | Newmarket, ON L3Y 6Z1
1-877-464-9675 ext. 71521 | niranjan.rajevan@york.ca | www.york.ca

Our Values: Integrity, Commitment, Accountability, Respect, Excellence



Our Mission: **Working together to serve our thriving communities – today and tomorrow**

Please consider the environment before printing this email.

SCHEDULE C: PUBLIC & APPLICANT CORRESPONDENCE

None

SCHEDULE D: PREVIOUS COA DECISIONS ON THE SUBJECT LAND

None