Tree Inventory Tree Removals Tree Preservation grading near trees. TREE PROTECTION PLAN NOTES Prior to site disturbance the owner must confirm that no migratory birds are making use of the site for nesting. The owner must ensure that the works are in conformance with the Migratory Bird Convention Act and that no migratory bird nests will be impacted by the proposed work. It is the applicants' responsibility to discuss potential tree injury of trees on shared property lines with their neighbours. Should such trees be injured to the point of instability or death the applicant may be held responsible for removal and such issues would be dealt with in civil Tree Label (GREEN) preservation recommended court or through negotiation. The applicant would be required to replace such trees to the satisfaction of the City of Vaughan. TREE PROTECTION ZONE: No construction activity including grade changes, surface treatments or excavations of any kind is permitted within the area identified on the Tree Protection Plan or Site Plan as a Tree Protection Zone (TPZ). No root cutting is permitted. No storage of materials or fill is permitted within the TPZ. No movement or storage of vehicles or equipment is permitted within the TPZ. Grade changes are not permitted within established TPZ. The area(s) identified as a TPZ must remain undisturbed at all times. TREE PROTECTION BARRIERS: For City-owned Trees: Tree protection barriers for trees situated on the City road allowance where visibility must be maintained, can be 1.2m (4ft.) high and consist of chain link, or orange plastic web snow fencing on a 2" x 4" wood frame. All supports and bracing used to secure the barrier should be located outside the TPZ. All supports and bracing should minimize damage to roots outside the Required tree protection fencing (heavy duty TPZ. Where some fill or excavate has to be temporarily located near a tree protection barrier, plywood must be used to ensure no material enters the TPZ. If the TPZ needs to be reduced to facilitate construction access, the tree protection barrier must be maintained at a lesser distance and the exposed TPZ protected with plywood and wood chips. This must first be Polygon limit approved by the City of Vaughan. For trees on private property situated on or adjacent to construction sites: Tree protection barriers must be installed around trees to be protected using plywood clad hoarding or an equivalent approved by the City of Vaughan. All supports and bracing to safely Approximate dripline secure the barrier should be outside the TPZ. All such supports and bracing should minimize damage to roots outside the TPZ. Prior to the commencement of any site activity the tree protection barriers specified on this plan must be installed and written notice provided to the City of Vaughan. Established tree protection zones must not be used as construction access, storage or staging areas. The tree protection barriers must remain in effective condition until all site activities including landscaping are complete. Written notice must be provided to the City of Vaughan prior to the removal of the tree protection barriers. ARBORICULTURAL WORK: Any roots or branches which extend beyond the TPZ indicated on this plan which require pruning, must be pruned by a qualified Arborist or other tree professional as approved by the City of Vaughan. All pruning of tree roots and branches must be in accordance with good arboricultural standards. Roots located outside the TPZ that have received approval from the City of Vaughan to be pruned must first be exposed by hand digging or by using a low pressure hydro vac method. This will allow a proper pruning cut and minimize tearing of the roots. The Arborist/tree professional retained to carry out crown or root pruning must contact the City of Vaughan no less than 48 hours prior to conducting any specified work. Note: When 1800mm drip line distance is not attainable, hoarding should be at least 3000mm from outside edge of tree trunk. → CONC. STM. Storm @ 0.50% Conc. NOTES: 1. Attachment of fence to trees to be preserved is not allowed. Ensure fence is continuous and is located beyond the drip line of trees to be preserved. VAUGHAN Fencing to be installed prior to start of construction. All supports and bracing should be inside the Tree Protection Zone. All such supports should minimize damaging roots outside the Tree Protection Barrier. HEAVY DUTY TREE HOARDING PROTECTION DETAIL (PLYWOOD) No Construction activity, grade changes, surface treatment or excavations of any kind is permitted DRAWN: JC APPROVED: KH DRAWING NO. NOT TO SCALE DATE: 04/07/2016 MLA 107A STUDIO tla [249.32] <u>[249.58]</u> <u>[249.84]</u> Project ATTACHMENT 7 9 December 2019 Scale 1:200

LEGEND

Refer to Table 1 of report dated 9 December 2019, revised 5 April 2021 for complete tree inventory information. Tree resources greater than 15cm on and within 6 metres of the subject area, and trees of all sizes within the road right-of-way were included in the inventory.

The removal of 46 trees and tree polygons is required to accommodate the proposed development as indicated with RED labels.

Preservation of three trees will be possible with appropriate tree protection measures. Trees identified for preservation are indicated with GREEN labels. Minimum Tree Preservation zones and required preservation fencing are indicated with magenta. TPZ circles represent minimum distances for construction and

Tree location estimated by KFCI

Minimum Tree Preservation Zone (MAGENTA CIRCLE), with radius in metres from edge of tree

Tree Label (RED) removal required

hoarding per Detail MLA 107A)

Issue/Revisions Date By Report Submission 13 Jan. '20 CB Report Revisions 11 May '20 CB Report Revisions 5 Apr. '21 CB Report Revisions 7 July '21 CB Report Revisions

Base Data: JD Barnes Ltd. (topo), One Riser Designs (site plan)



146 Lakeshore Road West PO Box 1267 Lakeshore W PO Oakville ON L6K 0B3 t: 289.837.1871 e: consult@kuntzforestry.ca

20 Champlain Boulevard, Suite 102 Toronto, ON L3H 2Z1

10316 Keele Street City of Vaughan, Ontario

Existing Conditions, Proposed Site Plan, Tree Inventory & Preservation Plan

P2275

Figure